### FENESTRATION ESTING **L** ABORATORY

780 E. Francis St., Unit "T", Ontario, CA 91761 • Ph. (909) 923-6260 • Fax (909) 923-6262

Report No. : A97D-134-2

Date

: August 04, 1997

Page

: 1 of 4

TESTED FOR

FLEETWOOD ALUMINUM

2485 Railroad Street Corona, CA 91720

1.0 **PURPOSE** 

The purpose of this report is to present the testing methods employed and the test results obtained during the performance testing of one (1) Aluminum Sliding Glass Door described in paragraph 4.0 of this report.

#### TEST REFERENCES 2.0

- Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors: 2.1 AAMA/NWWDA 101/I.S.2 - 97 SGD - C 30 . 182" x 96"
- CAWM 300 96 Forced Entry Resistance Tests for Sliding Glass Doors 2.2
  - .0 SUMMARY

The test results in paragraphs 5.0 and 6.0 indicate that the test sample described in paragraph 4.0 of this report complied with the performance requirements of the above referenced specifications.

SAMPLE SUBMITTED 4.0

SERIES:

3070 EX

CONFIGURATION:

XXP

FRAME SIZE:

181.63" x 95.88"

SASH SIZE:

Locking Panel, 61.63" x 94.00" - Center Panel, 60.75" x 94.00"

POCKET SIZE:

59.25" x 91.75" Daylight opening of frame in pocket.

GLASS:

All panels contained a single lite of 1/4" tempered glass.

GLAZING:

All panels were channel glazed with vinyl gasket.

WEEPAGE:

The sill sat on a sill pan that captured the water draining through the sill weep slots. Refer to the attached drawing for weep sizes and locations

and required sill pan size.

Report No. : A97D-134-2

Page : 2 of 4

VEATHERING:

The head air barrier was not used. Refer to the cross section drawings for a complete understanding of weatherstrip type and locations.

HARDWARE:

The lockstile contained an Adams Rite Mortice lock 45" from the bottom. When locked, the tongue of the lock engaged a keep which consisted of two (2) metal plates on either side of the jamb extrusion and fastened together with a single screw. Each active panel bottom rail contained an adjustable tandem steel roller at each end.

CONSTRUCTION:

The frame was mechanically joined with two (2) #10 x 3/4" PPH screws per comer.

The sill contained a) a stainless steel snap-in roller track for each sliding panel and b) a PVC snap-in filler in the pile pockets such that when all panels are close, no pile is visible from the outside. The bottom rail of all panels contained a PVC stiffener full length.

The center panel interlocked with an aluminum fixed interlock fastened to a 2" x 6" nominal wood stud with a pair of screws every 20". The fixed interlock butted up to the sill and head. A reinforced plywood wall enclosed the remainder of the frame so that there was no fixed lite but rather a wall pocket.

CAULKING:

All frame corners were sealed full profile.

All glazing corners were sealed inside and outside.

The fixed interlock was caulked full length to the supporting wood stud. The plywood wall was caulked full perimeter to the buck.

**ANCHORING:** 

The frame was fastened to the 2"  $\times$  8" wooden buck with #10  $\times$  2" PPH screws as follows:

- a) Jambs, sets of two (2) screws every 24".
- b) Head, sets of two (2) screws every 24".
- c) Sill, sets of two (2) screws every 24".

### 5.0 TEST PROCEDURES AND RESULTS

5.1 All testing procedures were performed in accordance with the performance requirements of the specifications referenced in paragraph 2.0 of this report.

Report No. : A97D-134-2

Page : 3 of 4

7.2	TEST RESULTS PARAGRAPH 2.1.2	TEST DESCRIPTION  Air Infiltration (ASTM E 283	MEASURED 3)	ALLOWED
		1.57 PSF The tested specimen meets/exceed 101/I.S.2 for Air Infiltration.	0.19 CFWFt <sup>2</sup>	0.3 CFM/Ft <sup>2</sup> in AAMA/NWWDA
	2.1.3	Water Penetration (ASTM 4.5 PSF With/without screen	E 547 & ASTM E 331) No Leakage	No Leakage
	2.1.4	Uniform Load Structural (A 45.00 PSF POS 45.00 PSF NEG	ASTM E 330) +0.03" -0.03"	0.37" Set 0.37" Set
	2.2.19.5.1	Operating Force Breakaway Motion	26 lbf. 12 lbf.	30 lbf. 20 lbf.
	2.2.19.5.2	Deglazing (ASTM E 987) 70 lbf. Stiles 50 lbf. Rails	0% 0%	Less than 100% Less than 100%

#### 2.1.8 CAWM 300 - 96 Forced Entry Resistance Tests for Sliding Glass Doors ٥.0

## 2.3.1 Type "I" Sliding Glass Door

# 6.1.2 Results of Operable Panel

	TEST	<u>RESULTS</u>	<u>DESCRIPTION</u>		
6.1.1		Passed	Disassembly		
6.1.2.1	Α	Passed	800# parallel load in direction to open panel.		
6.1.2.2	В	Passed	Repeat Test "A" with additional 200# perpendicular load, toward the interior.		
6.1.2.3	С	Passed	Repeat Test "A" with additional 200# perpendicular load, toward the exterior.		
6.1.2.4	G	Passed	Hand and Tool Manipulation Test		
6.1.2.5	D	Passed	Repeat Test "A" with operable panel lifted upward and applying 50# load at		
9 (47) 9 (47) 97			bottom rail near meeting stiles toward interior for inside slide and toward exterior for outside slide.		
6.1.2.6	E	Passed	Repeat Test "B" with operable panel lifted upward.		
6.1.2.7	F	Passed	Repeat Test "C" with operable panel lifted upward.		
3.1.2.8	G	Passed	Hand and Tool Manipulation		
6.1.5 Type "!" Sliding Glass Door - Fixed Panel: Not Applicable. There was no fixed panel but					

6.1.5 Type "I" Sliding Glass Door - Fixed Panel: Not Applicable. There was no fixed panel but rather a wall pocket.

Report No.

: A97D-134-2

Page

: 4 of 4

For a complete description of the tested sample refer to the attached cross section drawings.

Assembly and die drawings of frame members are on file and have been compared to the sample submitted. Test sample sections, drawings, and a copy of this report will be retained at the test laboratory for four years.

The above and preceding test results were obtained by using the applicable ASTM and CAWM Test Methods. This report does not constitute Certification of this product. Certification can only be granted by an approved Administrator/Validator.

NOTE: Based on AAMA Technical Interpretation #32, all products claiming ratings under the auspices of this test report must be glazed with the glass used in the test specimen described in this report without exception, unless it can be proven that a different glazing is equal to or better than what was tested.

Testing Completed: August 01, 1997 Report Completed: August 04, 1997

> Pete Cruz Test Engineer

Jim Cruz

Test Technician