



# Testing Evaluation Laboratories, Inc.

2002 Wood Court Suite 1 – Plant City, FL 33563  
Phone: 813-754-9887

## TEST RESULTS

Dade Lab Certification Number: 11-1213.01

Test Notification Number: TEL 13-005

Report No: TEL 01991006

Test Dates: January 13-20, 2014

Report Date: March 21, 2014

### Issued to:

Fleetwood Windows and Doors  
1 Fleetwood Way  
Corona, CA 92879

**Project Summary:** Testing Evaluation Laboratories, Inc. (TEL) was contracted by Fleetwood Windows and Doors to perform tests on the Kona 3800 Fixed Windows at TEL's Plant City, FL test facility.

Test specimen descriptions and results are reported herein.

**Test Specifications:** The test specimens were evaluated in accordance with the following:

*High Velocity Hurricane Zone Protocols TAS 202-94, TAS 201-94 and TAS 203-94*

### Test Specimen Description:

<b>Series / Model:</b>	Kona 3800 Fixed Windows
<b>Type:</b>	Aluminum Fixed Windows
<b>Overall Size:</b>	60.00" x 120.00" – Specimens 1, 1a, 1b and 1c – (O) – Direct Mount 50.00" x 144.00" – Specimens 2 and 2a – (O) – Fin Mount 60.00" x 120.00" – Specimen 3 – (O) – Fin Mount 96.00" x 120.00" – Specimens 4 and 4a– (O/O/O) – Direct Mount 120.00" x 96.00" – Specimens 5 and 5a– (OOO) – Fin Mount
<b>Daylight Opening:</b>	57.10" x 117.10" – Specimens 1, 1a, 1b and 1c – (O) 47.10" x 141.10" – Specimens 2 and 2a – (O) 57.10" x 117.10" – Specimen 3 – (O) 93.06" x 37.375" – Specimens 4 and 4a– (O/O/O) - Top/Bottom Panels 93.06" x 37.50" – Specimens 4 and 4a– (O/O/O) – Center Panel 37.375" x 93.06" – Specimens 5 and 5a– (OOO) - End panels 37.50" x 93.06" – Specimens 5 and 5a– (OOO) - Center panel

**Test Specimen Description: Continued**

**Glazing Detail:** See attached drawing numbers L-7030, L-7108 and L-7109 for glazing details.

**Frame Material:** Aluminum

**Finish:** Mill Finish

**For Tested Elevation, Vertical Cross Sections, Horizontal Cross Sections, Components, Frame Anchoring, Glazing Detail and Bill of Materials See Attached Drawing numbers L-7030, L-7108 and L-7109.**

**SEQUENCE OF TESTS PERFORMED:**

**STRUCTURAL TESTS (TAS 202)**

**Specimen 1 – 60.0” x 120.0” Aluminum Fixed Window (O) – Direct Mount**

Design Pressure	Positive 60.0	Negative 60.0		
Air Infiltration (ASTM E283-04)	Pressure 1.57 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass	
Air Infiltration (ASTM E283-04)	Pressure 6.24 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass	

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)
Half Test Positive	30	30.00
Design Positive	30	60.00
Half Test Negative	30	30.00
Design Negative	30	60.00

Water Infiltration (ASTM E331-00)	Pressure	Time	Result
	15.0 PSF	15.0 Min.	Pass

**Note #1: Water Infiltration performed after Positive and Negative half and design loads.**

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)	Location	Deflection	Set	Allowable (Set)
Half Proof Positive	10	45.00				
Test Positive	30	90.00	1	0.035"	0.000"	0.048"
Half Proof Negative	10	45.00				
Test Negative	30	90.00	1	0.051"	0.005"	0.048"

**Deflection Locations:**

**Location 1 – Center of Anchors**

**Forced Entry** Passed – No Entry

**Conclusion:** TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

James Hayhurst, Test Technicians

**SEQUENCE OF TESTS PERFORMED:**

**STRUCTURAL TESTS (TAS 202)**

**Specimen 2 – 50.0" x 144.0" Aluminum Fixed Window (O) – Fin Mount**

Design Pressure	Positive 65.0	Negative 65.0		
Air Infiltration (ASTM E283-04)	Pressure 1.57 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass	
Air Infiltration (ASTM E283-04)	Pressure 6.24 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass	

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)
Half Test Positive	30	32.50
Design Positive	30	65.00
Half Test Negative	30	32.50
Design Negative	30	65.00

Water Infiltration (ASTM E331-00)	Pressure 15.0 PSF	Time 15.0 Min.	Result Pass
-----------------------------------	----------------------	-------------------	----------------

**Note #1: Water Infiltration performed after Positive and Negative half and design loads.**

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)	Location	Deflection	Set	Allowable (Set)
Half Proof Positive	10	45.00				
Test Positive	30	90.00	1	0.005"	0.001"	0.048"
Half Proof Negative	10	45.00				
Test Negative	30	90.00	1	0.013"	0.007"	0.048"

**Deflection Locations:**

**Location 1 – Center of Anchors**

**Forced Entry** Passed – No Entry

**Conclusion:** TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

James Hayhurst, Test Technicians

**SEQUENCE OF TESTS PERFORMED:**

**STRUCTURAL TESTS (TAS 202)**

**Specimen 3 – 60.0” x 120.0” Aluminum Fixed Window (O) – Fin Mount**

Design Pressure	Positive 60.0	Negative 60.0	
Air Infiltration (ASTM E283-04)	Pressure 1.57 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass
Air Infiltration (ASTM E283-04)	Pressure 6.24 PSF	SCFM/Ft <sup>2</sup> 0.000	Result Pass

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)
Half Test Positive	30	30.00
Design Positive	30	60.00
Half Test Negative	30	30.00
Design Negative	30	60.00

Water Infiltration (ASTM E331-00)	Pressure 15.0 PSF	Time 15.0 Min.	Result Pass
-----------------------------------	----------------------	-------------------	----------------

**Note #1: Water Infiltration performed after Positive and Negative half and design loads.**

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)	Location	Deflection	Set	Allowable (Set)
Half Proof Positive	10	45.00				
Test Positive	30	90.00	1	0.006"	0.002"	0.048"
Half Proof Negative	10	45.00				
Test Negative	30	90.00	1	0.006"	0.001"	0.048"

**Deflection Locations:**

**Location 1 – Center of Anchors**

**Forced Entry** Passed – No Entry

**Conclusion:** TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

James Hayhurst, Test Technicians



**SEQUENCE OF TESTS PERFORMED:**

**STRUCTURAL TESTS (TAS 202)**

**Specimen 5 – 96.0" x 120.0" Triple Mulled Aluminum Fixed Window (O/O/O)**

**Design Pressure            Positive 65.0    Negative 65.0**

**Structural Loads (ASTM E330-02)**

<b>Range</b>	<b>Time (sec)</b>	<b>Load (psf)</b>	<b>Location</b>	<b>Deflection</b>	<b>Allowable (Def)</b>
Half Test Positive	30	32.50			
Design Positive	30	65.00	1	0.469"	0.517"
Half Test Negative	30	32.50			
Design Negative	30	65.00	1	0.445"	0.517"

**Structural Loads (ASTM E330-02)**

<b>Range</b>	<b>Time (sec)</b>	<b>Load (psf)</b>	<b>Location</b>	<b>Deflection</b>	<b>Set</b>	<b>Allowable (Set)</b>
Half Proof Positive	10	45.00				
Test Positive	30	90.00	1	0.688"	0.017"	0.372"
Half Proof Negative	10	45.00				
Test Negative	30	90.00	1	0.683"	0.005"	0.372"

***Deflection Locations:***

***Location 1 – Center of Anchors***

**Conclusion:** TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

James Hayhurst, Test Technicians

**SEQUENCE OF TESTS PERFORMED:**

**STRUCTURAL TESTS (TAS 202)**

**Specimen 5 – 120.0” x 96.0” Triple Mulled Aluminum Fixed Window (OOO)**

Design Pressure	Positive 65.0	Negative 75.0		
Air Infiltration (ASTM E283-04)	Pressure 1.57 PSF	SCFM/Ft <sup>2</sup> 0.000	Result	Pass
Air Infiltration (ASTM E283-04)	Pressure 6.24 PSF	SCFM/Ft <sup>2</sup> 0.000	Result	Pass

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)
Half Test Positive	30	32.50
Design Positive	30	65.00
Half Test Negative	30	37.50
Design Negative	30	75.00

Water Infiltration (ASTM E331-00)	Pressure	Time	Result
	15.0 PSF	15.0 Min.	Pass

**Note #1: Water Infiltration performed after Positive and Negative half and design loads.**

**Structural Loads (ASTM E330-02)**

Range	Time (sec)	Load (psf)	Location	Deflection	Set	Allowable (Set)
Half Proof Positive	10	48.75				
Test Positive	30	97.50	1	0.583"	0.002"	0.372"
Half Proof Negative	10	46.25				
Test Negative	30	112.50	1	0.610"	0.005"	0.372"

**Deflection Locations:**

**Location 1 – Center of Anchors**

**Forced Entry** Passed – No Entry

**Conclusion:** TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

James Hayhurst, Test Technicians

## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 1A – 60.0" x 120.0" Aluminum Fixed Window – (O)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
74°F	D	9.0 lbs, 3 oz.	8'-0"	17'0"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	52.5"	111.0"	49.9 fps
2	Pass	30.0"	60.0"	50.2 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.71
0% to 60%	0.0 to 39.0	300	2.98
50% to 80%	32.5 to 52.0	600	2.41
30% to 100%*	19.5 to 65.0	100	2.91

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	2.99
50% to 80%	32.5 to 52.0	1050	2.27
0% to 60%	0.0 to 39.0	50	2.98
20% to 50%	13.0 to 32.5	3350	2.90
*Panel deflected 1.25" from original plane at 100% Positive load and 3.13" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.			

Jarrett Wright and James Hayhurst, Test Technicians

Mfg Observers – Joe Zammit



## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 1B – 60.0" x 120.0" Aluminum Fixed Window – (O)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
74°F	D	9.0 lbs, 3 oz.	8'-0"	17'0"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	30.0"	60.0"	49.9 fps
2	Pass	8.0"	8.0"	50.1 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling      Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.84
0% to 60%	0.0 to 39.0	300	2.97
50% to 80%	32.5 to 52.0	600	2.99
30% to 100%*	19.5 to 65.0	100	2.89

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	2.99
50% to 80%	32.5 to 52.0	1050	2.51
0% to 60%	0.0 to 39.0	50	2.97
20% to 50%	13.0 to 32.5	3350	2.89
*Panel deflected 1.00" from original plane at 100% Positive load and 3.25" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.			

Jarrett Wright and James Hayhurst, Test Technicians

Mfg. Observers – Joe Zammit

## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 1C – 60.0" x 120.0" Aluminum Fixed Window – (O)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
74°F	D	9.0 lbs, 3 oz.	8'-0"	17'0"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	52.50"	111.00"	50.1 fps
2	Pass	30.00"	60.00"	50.0 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.93
0% to 60%	0.0 to 39.0	300	2.99
50% to 80%	32.5 to 52.0	600	2.35
30% to 100%*	19.5 to 65.0	100	2.19

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	2.98
50% to 80%	32.5 to 52.0	1050	2.27
0% to 60%	0.0 to 39.0	50	2.99
20% to 50%	13.0 to 32.5	3350	2.58

\*Panel deflected 1.06" from original plane at 100% Positive load and 3.75" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

Jarrett Wright and James Hayhurst, Test Technicians

Mfg. Observers – Joe Zammit

## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 2A – 54.0" x 144.0" Aluminum Fixed Window – (O)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
75°F	D	9.0 lbs, 2 oz.	8'-1/4"	17'1"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	24.00"	72.00"	50.1 fps
2	Pass	42.00"	9.00"	49.8 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.40
0% to 60%	0.0 to 39.0	300	2.99
50% to 80%	32.5 to 52.0	600	2.14
30% to 100%*	19.5 to 65.0	100	3.00

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	2.99
50% to 80%	32.5 to 52.0	1050	2.08
0% to 60%	0.0 to 39.0	50	2.98
20% to 50%	13.0 to 32.5	3350	2.65
*Panel deflected 2.13" from original plane at 100% Positive load and 3.63" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.			

Jarrett Wright and James Hayhurst, Test Technicians

Mfg. Observers – Joe Zammit



## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 4A – 96.0" x 120.0" Triple Muller Aluminum Fixed Window – (O/O/O)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
76°F	D	9.0 lbs, 3 oz.	8'-0"	17'1"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	60.00"	48.00"	49.9 fps
2	Pass	80.00"	48.00"	50.1 fps
3	Pass	72.50"	8.00"	50.0 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.64
0% to 60%	0.0 to 39.0	300	2.90
50% to 80%	32.5 to 52.0	600	2.00
30% to 100%*	19.5 to 65.0	100	2.98

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	3.00
50% to 80%	32.5 to 52.0	1050	1.87
0% to 60%	0.0 to 39.0	50	2.92
20% to 50%	13.0 to 32.5	3350	2.07

\*Panel deflected 2.00" from original plane at 100% Positive load and 1.38" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

Jarrett Wright and James Hayhurst, Test Technicians

Mfg. Observers – Joe Zammit



## IMPACT AND CYCLING TESTS (TAS 201/203)

### Specimen 5A – 120.0" x 96.0" Triple Muller Aluminum Fixed Window – (OOO)

#### TAS 201 and 203 – Large Missile Impact (2 x 4 Southern Yellow Pine)

Cond. Temp Of Specimen	Missile Level	Missile Weight	Missile Length	Muzzle Distance From Specimen
75°F	D	9.0 lbs, 2 oz.	8'-1/4"	17'1"

Impact Location	Results	X - Measurement	Y - Measurement	Speed
1	Pass	48.00"	80.00"	50.1 fps
2	Pass	48.00"	59.00"	49.7 fps
3	Pass	88.00"	72.00"	49.9 fps
Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen. "Y" measurement is from the bottom edge of test specimen.				

#### TAS 201 and 203– Fatigue Load Cycling Design Pressure +65.0 psf / -65.0 psf

Positive % of Test Load	Positive Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
20% to 50%	13.0 to 32.5	3500	2.72
0% to 60%	0.0 to 39.0	300	2.91
50% to 80%	32.5 to 52.0	600	2.90
30% to 100%*	19.5 to 65.0	100	2.99

Negative % of Test Load	Negative Pressure Range (psf)	Number Of Cycles	Average Cycle Time (Sec)
30% to 100%*	19.5 to 65.0	50	3.00
50% to 80%	32.5 to 52.0	1050	2.17
0% to 60%	0.0 to 39.0	50	2.97
20% to 50%	13.0 to 32.5	3350	2.61

\*Panel deflected 2.00" from original plane at 100% Positive load and 2.13" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

Jarrett Wright and James Hayhurst, Test Technicians

Mfg. Observers – Joe Zammit

## Conditions, Terms, and General Notes Regarding These Tests

The product tested Has Been compared to the detailed drawing, bill of materials and fabrication information supplied by the client so named herein. Our analysis, which includes dimensional and component description comparisons, indicate the tested product and engineering information supplied by the client "Are Equivalent". The report and representative samples will be retained for four years from the date of initial test.

These test results were obtained by employing all requirements of the designated test methods with no Deviations unless explicitly noted in test report. The test results and specimen supplied for testing are in compliance with the reference.

The test results are specific to the product tested by this laboratory and of the sample supplied by the client named herein, and they relate to no other product either manufactured by the client, a fabricator of the client or of the client or of installed field performance.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.


Testing Evaluation Laboratories, Inc. makes no opinions or endorsements regarding this product and its performance. This report may not be reproduced or quoted in partial form without the expressed written approval of Testing Evaluation Laboratories, Inc.

Testing Evaluation Laboratories, Inc.'s letter, reports, its name or insignia or mark are for the exclusive use of the client so named herein and any other use is strictly prohibited. The report, letters and the name of Testing Evaluation Laboratories, Inc., its seal or mark shall not be used in any circumstance to the general public or in any advertising.

Limitation of liability: Due diligence was used in performing the tests and reporting the results. By acceptance of this report, this client agrees to hold harmless and indemnify Testing Evaluation Laboratories, Inc., its employees, sub-contractors, officers and owners against all claims and demands of any kind whatsoever, which arise out of or in any manner connected with the performance of work referred to herein.

Testing Evaluation Laboratories, Inc.

  
Vivian K. Wright,  
President

  
4/16/2024  
William B. Shelton, P.E.  
Florida P.E. # 26686

**Revision Log**


Rev No.	Date	Page(s)	Revision(s)
0	3/21/2014	NA	Original Report Issue

TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	Table of contents
2	Test elevation
3	Horizontal and vertical cross sections
4	Frame anchoring
5	Bill of materials, components and glazing detail

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations/Noted - TEL # 0199/0006  
 Date 3/21/14 verified by *[Signature]*

PRODUCT: FLEETWOOD	
PART OR ASSEMBLY: TABLE OF CONTENTS	
	REVISIONS
	NO. DATE BY
	
DATE: 9/25/13	
SCALE: N.T.S.	
DWG. BY: JK	
CHK. BY: LFS	
DRAWING NO.: L-7030	
SHEET 1 OF 5	





SPEC. #1, 1A, 1B, 1C

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted TEL # 01991006  
 Date 3/21/14 Verified by *[Signature]*




DATE: 9/25/13  
 SCALE: N.T.S.  
 DWG. BY: JK  
 CHK. BY: LFS  
 DRAWING NO.: L-7030  
 SHEET 2 OF 5



NO.	DATE	REVISIONS	BY

PRODUCT: FLEETWOOD  
 PART OR ASSEMBLY: TEST ELEVATIONS

**3** HORIZONTAL CROSS SECTION



**1** VERTICAL CROSS SECTION



**2** VERTICAL CROSS SECTION

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviation Noted - TEL # 01991096  
 Date 3/21/14 verified by [Signature]

PRODUCT: FLEETWOOD		PART OR ASSEMBLY: VERTICAL AND HORIZONTAL CROSS SECTIONS	
NO.	DATE	BY	REVISIONS
 <b>RW</b> BUILDING CONSULTANTS, INC. 813.659.9197			
DATE: 9/25/13			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7030			
SHEET <u>3</u> OF <u>5</u>			








**BILL OF MATERIALS**

ITEM #	DESCRIPTION	MATERIAL
B	2X BUCK SG >= 0.55	WOOD
C	1/4" MAX. SHIM SPACE	-
G	#10 x 2" PFH WOOD SCREW	STEEL
2	KONA BLOCK FRAME	6063-T6 ALUM
3	GLASS STOP (1-1/4")	6063-T6 ALUM
12	SHEAR BLOCK	ALUM
40	#10 X 1" PPH SMS	STEEL
51	MINI BULB VINYL (EPDM 70 DUROMETER)-TREMCO	-
55	SETTING BLOCK	-


Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted: TEL # 01991006  
 Date 3/21/14 verified by *elles*



PRODUCT: FLEETWOOD	
PART OR ASSEMBLY: BILL OF MATERIALS, COMPONENTS AND GLAZING DETAIL	
NO.	DATE
BY	REVISIONS
<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>RW</b> BUILDING CONSULTANTS, INC.                  813.659.9197             </div>	
DATE: 9/25/13	
SCALE: N.T.S.	
DWG. BY: JK	
CHK. BY: LFS	
DRAWING NO.: L-7030	
SHEET 5 OF 5	








**SPEC. #3**

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviation Noted - TEL # 0199 1006  
 Date: 3/21/14 certified by: *[Signature]*

PRODUCT: FLEETWOOD		PART OR ASSEMBLY: TEST ELEVATIONS	
NO.	DATE	BY	REVISIONS
<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>RW</b> BUILDING CONSULTANTS, INC.            813.659.9197         </div>			
DATE: 1/14/14			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7108			
SHEET <u>2</u> OF <u>8</u>			



**SPEC. #2, 2A**

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted - TEL # 01991006  
 Date 3/21/14 verified by *ellw*

**RW** BUILDING  
 CONSULTANTS, INC.  
 813.659.9197

DATE: 1/14/14  
 SCALE: N.T.S.  
 DWG. BY: JK  
 CHK. BY: LFS  
 DRAWING NO.:  
 L-7108  
 SHEET 3 OF 8


PRODUCT:		PART OR ASSEMBLY:	
FLEETWOOD		TEST ELEVATION	
NO.	DATE	REVISIONS	BY







Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted. TEL # 0199 1006  
 Date 3/21/14 Verified by *[Signature]*



**FRAME ANCHORING W/ FIN**  
 2X buck construction



DATE: 1/14/14

SCALE: N.T.S.

DWG. BY: JK

CHK. BY: LFS

DRAWING NO.:  
 L-7108

SHEET 6 OF 8


PRODUCT:

FLEETWOOD


PART OR ASSEMBLY:

FRAME ANCHORING


NO.	DATE	REVISIONS	BY




1 KONA FIN FRAME



3 GLASS STOP 1-1/4"



12 SHEAR BLOCK



C GLAZING DETAIL

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted TEL # 81991096  
 Date 3/21/14 Verified by [Signature]

PRODUCT:		FLEETWOOD	
PART OR ASSEMBLY:		COMPONENTS AND GLAZING DETAILS	
NO.	DATE	BY	REVISIONS
 <b>RW BUILDING CONSULTANTS, INC.</b> 813.659.9197			
DATE: 1/14/14			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7108			
SHEET 7 OF 8			

**BILL OF MATERIALS**

ITEM #	DESCRIPTION	MATERIAL
B	2X BUCK SG >= 0.55	WOOD
C	1/4" MAX. SHIM SPACE	-
G	#10 x 2" PFH WOOD SCREW	STEEL
F	#10 x 1-1/2" PPH WOOD SCREW	STEEL
1	KONA FIN FRAME	6063-T6 ALUM
3	GLASS STOP (1-1/4")	6063-T6 ALUM
12	SHEAR BLOCK	ALUM
40	#10 X 1" PPH SMS	STEEL
51	MINI BULB VINYL (EPDM 70 DUROMETER)-TREMCO	-
55	SETTING BLOCK	-

Testing Evaluation Laboratories Inc  
 Specimens Complies with Drawing  
 Deviations Noted. TEL # 0199 1006  
 Date 2/21/14 Verified by *elc*

NO.	DATE	REVISIONS	BY


PRODUCT:	FLEETWOOD
PART OR ASSEMBLY:	BILL OF MATERIALS



DATE:	1/14/14
SCALE:	N.T.S.
DWG. BY:	JK
CHK. BY:	LFS
DRAWING NO.:	L-7108
SHEET	8 OF 8








Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted. TEL # 0199.1096  
 Date 3/21/14 Verified by *[Signature]*


**SPEC. #5, 5A**

PRODUCT: FLEETWOOD		PART OR ASSEMBLY: TEST ELEVATION	
NO.	DATE	REVISIONS	BY
<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>RW</b> BUILDING CONSULTANTS, INC.        813.659.9197     </div>			
DATE: 1/15/14			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7109			
SHEET <u>2</u> OF <u>10</u>			




**SPEC. #4, 4A**

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted TEL. # 0199 1904  
 Date 3/21/14 Verified by JMK


PRODUCT: FLEETWOOD		PART OR ASSEMBLY: TEST ELEVATION	
NO.	DATE	BY	REVISIONS
			
DATE: 1/15/14			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7109			
SHEET 3 OF 10			





SEE NOTE 1

**1**  
**4** VERTICAL CROSS SECTION




SEE NOTE 1


**4**  
**4** VERTICAL CROSS SECTION

Testing Evaluation Laboratories Inc  
Specimen Complies with Drawing  
Deviations Noted - TEL # 0199 1006  
Date 3/21/14 Verified by *SULLO*

NOTE:  
1. Item #11 located 6" from each end and one in center (3) total.



**2**  
**4** HORIZONTAL CROSS SECTION




**3**  
**4** HORIZONTAL CROSS SECTION


PRODUCT: FLEETWOOD		PART OR ASSEMBLY: VERTICAL AND HORIZONTAL CROSS SECTIONS	
NO.	DATE	BY	REVISIONS
DATE: 1/15/14			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: L-7109			
SHEET 4 OF 10			




NOTE:  
 1. Item #11 located 6" from each end and one in center (3) total.




**1**  
**5** VERTICAL CROSS SECTION




**3**  
**5** HORIZONTAL CROSS SECTION



**2**  
**5** VERTICAL CROSS SECTION



**4**  
**5** HORIZONTAL CROSS SECTION



**5**  
**5** HORIZONTAL CROSS SECTION

Testing Evaluation Laboratories Inc  
 Specimen Complies with Drawing  
 Deviations Noted - TEL # 01991006  
 Date 3/21/14 Verified by JPL

PRODUCT: FLEETWOOD	
PART OR ASSEMBLY: VERTICAL AND HORIZONTAL CROSS SECTIONS	
NO.	DATE
BY	REVISIONS
 RW BUILDING CONSULTANTS, INC. 813.659.9197	
DATE: 1/15/14	
SCALE: N.T.S.	
DWG. BY: JK	
CHK. BY: LFS	
DRAWING NO.: L-7109	
SHEET 5 OF 10	













