

Testing Evaluation Laboratories, Inc.

2002 Wood Court Suite 1 – Plant City, FL 33563 Phone: 813-754-9887

TEST RESULTS

Dade Lab Certification Number: 15-0114.08 Test Notification Number: TEL 15-004 Report No:

TEL 01991350

Test Dates:

March 16, 2015

through April 3, 2015

Report Date:

June 26, 2015

Issued to:

Fleetwood Windows and Doors 1 Fleetwood Way Corona, CA 92879

Project Summary: Testing Evaluation Laboratories, Inc. (TEL) was contracted by Fleetwood Windows and Doors to perform tests on the 3900-T Side Hinged Doors at TEL's Plant City, FL test facility.

Test specimen descriptions and results are reported herein.

Test Specifications:

The test specimens were evaluated in accordance with the following:

High Velocity Hurricane Zone Protocols TAS 202-94, TAS 201-94 and TAS 203-94

Test Specimen Description:

Series / Model:

3900-T Side Hinged Doors

Type:

Aluminum Side Hinged Doors

Overall Size:

169.00" x 120.00" - All Specimens - (OXO)

Daylight Opening:

35.00" x 108.00" - Door Panel - All Specimens

57.00" x 117.00" - 3800-T Sidelite- Specimen 6 and 6a

47.00" x 108.00" - Sash Sidelite - All Specimens

Glazing Details:

See attached drawings for glazing details.

Frame Material:

Aluminum

Finish:

Mill Finish

For Tested Elevation, Vertical Cross Sections, Horizontal Cross Sections, Components, Frame Anchoring, Glazing Detail and Bill of Materials See Attached Drawing numbers L-7349 and L-7349A.

STRUCTURAL TESTS (TAS 202)

Specimen 1 – 169.00" x 120.00" – Outswing Door with (1) 3800-T Sidelite and (1) Sash Sidelite – OXO

| Air Infiltration (ASTM E283-04) Pressure 1.57 PSF 0.007 Result 0.007 Pass 0.001 Pass 0.001 <th< th=""><th>Design Pressure Positive 65.0</th><th>Negative 65.0</th><th></th><th></th></th<> | Design Pressure Positive 65.0 | Negative 65.0 | | |
|---|-----------------------------------|---------------|-------------------------------|--------|
| Air Exfiltration (ASTM E283-04) Pressure 1.57 PSF Pressure 1.57 PSF Pressure 2.50 Pass SCFM/Ft^2 Pass Result Pressure 2.50 Pass Air Infiltration (ASTM E283-04) Pressure 6.24 PSF Pressure 2.62 PSF Pressure 2.62 PResult Pressure 3.62 PRESSURE 2.62 PRESSURE 3.62 PRESSUR | Air Infiltration (ASTM E283-04) | | | |
| Air Infiltration (ASTM E283-04) Pressure SCFM/Ft^2 Result 6.24 PSF 0.003 Pass Air Exfiltration (ASTM E283-04) Pressure SCFM/Ft^2 Result | Air Exfiltration (ASTM E283-04) | Pressure | SCFM/Ft^2 | Result |
| Air Exfiltration (ASTM E283-04) Pressure SCFM/Ft^2 Result | Air Infiltration (ASTM E283-04) | | | 8 2255 |
| | Air Evelitration (ACTA) E202 04) | | 7.15.0.00 | |
| | All Exhibitation (ASTIVI E285-04) | | 1000 1000 0000 0000 0000 0000 | |

Structural Loads (ASTM E330-02)

| Range | Time (sec) | Load (psf) | Locatio | n Deflection | Allowable (Def) |
|--------------------------|---------------|---------------------|---------|-------------------|-----------------|
| Half Test Positive | 30 | 32.50 | | | |
| Design Positive | 30 | 65.00 | 1 | 0.488" | 0.667" |
| Half Test Negative | 30 | 32.50 | | | |
| Design Negative | 30 | 65.00 | 1 | 0.521" | 0.667" |
| Water Infiltration (ASTN | 1 E331-00) | Pressure 9.75 PS | | Time 15.0 Min. | Result Pass |

Note #1: Water Infiltration performed after Positive and Negative half and design loads.

Structural Loads (ASTM E330-02)

| Range | Time (sec) | Load (psf) | Location | Deflection | Set | Allowable | (Set) |
|--------------------------------------|---------------|----------------|----------|------------------|------|-----------|--------------------|
| Half Proof Positive Test Positive | 10 30 | 48.75 97.50 | 1 2 | 0.695" 0.069" | 0.00 | | 0.480'' 0.208'' |
| Half Proof Negative Test Negative | 10 30 | 48.75 97.50 | 1 2 | 0.775" 0.350" | 0.00 | E CES | 0.480" 0.208" |

Deflection Locations:

Location 1 - Center of Mullion; Location 2 - Between locking points on latch stile.

Forced Entry Passed – No Entry

Conclusion: TEL observed no signs of failure in any area of this test specimen during the Uniform Static Load Test. In addition, specimen met the permanent set requirements. Therefore, this specimen satisfies the uniform static load test requirements of TAS 202-94.

Specimen 6a - 169.00" x 120.00" - Outswing Door with (1) 3800-T Sidelite and (1) Sash Sidelite - OXO

TAS 201-94/TAS 203-94 - Large Missile Impact (2 x 4 Southern Yellow Pine)

| Cond. Temp | Missile | Missile | Missile | Muzzle Distance |
|-------------|---------|----------------|---------|-----------------|
| Of Specimen | Level | Weight | Length | From Specimen |
| 77°F | D | 9.0 lbs, 0 oz. | 8'-1/4" | 17'0" |

| Impact Location | Results | X - Measurement | Y - Measurement | Speed |
|--------------------|---------|-----------------|-----------------|----------|
| 1 | Pass | 31.25 " | 60.25 " | 50.1 fps |
| 2 | Pass | 53.50" | 8.00" | 50.0 fps |
| 3 | Pass | 61.75" | 60.50" | 50.1 fps |
| 4 | Pass | 85.75" | 60.00" | 50.1 fps |
| 5 | Pass | 97.25 " | 11.50" | 50.0 fps |

Orientation of Missile at Impact was within +/-5° of horizontal.

None of the impacts penetrated the specimens.

"X" measurement is from the left edge of test specimen.

"Y" measurement is from the bottom edge of test specimen.

TAS 201-94/TAS 203-94 - Fatigue Load Cycling

Design Pressure +50.0 psf / - 55.0 psf

| Positive % of Test Load | Positive Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 20% to 50% | 10.0 to 25.0 | 3500 | 1.33 |
| 0% to 60% | 0.0 to 30.0 | 300 | 1.95 |
| 50% to 80% | 25.0 to 40.0 | 600 | 1.32 |
| 30% to 100%* | 15.0 to 50.0 | 100 | 1.75 |

| Negative % of Test Load | Negative Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 30% to 100%* | 16.5 to 55.0 | 50 | 1.71 |
| 50% to 80% | 27.5 to 44.0 | 1050 | 1.21 |
| 0% to 60% | 0.0 to 33.0 | 50 | 2.13 |
| 20% to 50% | 11.0 to 27.5 | 3350 | 1.17 |

^{*}Active Panel deflected 1.75" from original plane at 100% Positive load and 2.25" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

Specimen 6c - 169.00" x 120.00" - Outswing Door with Sash Sidelites - OXO

TAS 201-94/TAS 203-94 - Large Missile Impact (2 x 4 Southern Yellow Pine)

| Cond. Temp | Missile | Missile | Missile | Muzzle Distance |
|-------------|---------|----------------|---------|-----------------|
| Of Specimen | Level | Weight | Length | From Specimen |
| 77°F | D | 9.0 lbs, 1 oz. | 8'-1/2" | 17'0" |

| Impact Location | Results | X - Measurement | Y - Measurement | Speed |
|--------------------|---------|-----------------|-----------------|----------|
| 1 | Pass | 30.00" | 60.00" | 50.0 fps |
| 2 | Pass | 60.25" | 61.00" | 49.9 fps |
| 3 | Pass | 84.50" | 59.25" | 50.1 fps |
| 4 | Pass | 96.00" | 11.50" | 50.0 fps |
| 5 | Pass | 47.50" | 11.25" | 50.1 fps |

Orientation of Missile at Impact was within +/-5° of horizontal. None of the impacts penetrated the specimens. "X" measurement is from the left edge of test specimen.

"Y" measurement is from the bottom edge of test specimen.

TAS 201-94/TAS 203-94 - Fatigue Load Cycling

Design Pressure +65.0 psf / - 65.0 psf

| Positive % of Test Load | Positive Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 20% to 50% | 13.0 to 32.5 | 3500 | 1.99 |
| 0% to 60% | 0.0 to 39.0 | 300 | 1.21 |
| 50% to 80% | 32.5 to 52.0 | 600 | 1.31 |
| 30% to 100%* | 19.5 to 65.0 | 100 | 1.41 |

| Negative % of Test Load | Negative Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 30% to 100%* | 19.5 to 65.0 | 50 | 1.65 |
| 50% to 80% | 32.5 to 52.0 | 1050 | 1.63 |
| 0% to 60% | 0.0 to 39.0 | 50 | 1.99 |
| 20% to 50% | 13.0 to 32.5 | 3350 | 2.29 |

^{*}Active Panel deflected 2.75" from original plane at 100% Positive load and 3.00" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

Specimen 6d - 169.00" x 120.00" - Outswing Door with Sash Sidelites - OXO

TAS 201-94/TAS 203-94 - Large Missile Impact (2 x 4 Southern Yellow Pine)

| Cond. Temp | Missile | Missile | Missile | Muzzle Distance |
|-------------|---------|----------------|---------|-----------------|
| Of Specimen | Level | Weight | Length | From Specimen |
| 77°F | D | 9.0 lbs, 1 oz. | 8'-1/2" | 17'0" |

| Impact Location | Results | X - Measurement | Y - Measurement | Speed |
|--------------------|---------|-----------------|-----------------|----------|
| 1 | Pass | 47.25" | 11.375" | 50.0 fps |
| 2 | Pass | 95.75" | 11.50" | 50.0 fps |
| 3 | Pass | 84.25" | 59.50" | 50.1 fps |
| 4 | Pass | 60.25" | 60.50" | 49.9 fps |
| 5 | Pass | 30.25" | 59.50" | 50.0 fps |

Orientation of Missile at Impact was within +/-5° of horizontal.

None of the impacts penetrated the specimens.

TAS 201-94/TAS 203-94 – Fatigue Load Cycling

Design Pressure +65.0 psf / -65.0 psf

| Positive % of Test Load | Positive Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 20% to 50% | 13.0 to 32.5 | 3500 | 1.99 |
| 0% to 60% | 0.0 to 39.0 | 300 | 2.29 |
| 50% to 80% | 32.5 to 52.0 | 600 | 2.31 |
| 30% to 100%* | 19.5 to 65.0 | 100 | 2.74 |

| Negative % of Test Load | Negative Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 30% to 100%* | 19.5 to 65.0 | 50 | 2.99 |
| 50% to 80% | 32.5 to 52.0 | 1050 | 2.25 |
| 0% to 60% | 0.0 to 39.0 | 50 | 1.89 |
| 20% to 50% | 13.0 to 32.5 | 3350 | 1.71 |

*Active Panel deflected 3.625" from original plane at 100% Positive load and 4.00" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

[&]quot;X" measurement is from the left edge of test specimen.

[&]quot;Y" measurement is from the bottom edge of test specimen.

Specimen 6e - 169.00" x 120.00" - Outswing Door with Sash Sidelites - OXO

TAS 201-94/TAS 203-94 - Large Missile Impact (2 x 4 Southern Yellow Pine)

| Cond. Temp | Missile | Missile | Missile | Muzzle Distance |
|-------------|---------|----------------|---------|-----------------|
| Of Specimen | Level | Weight | Length | From Specimen |
| 77°F | D | 9.0 lbs, 1 oz. | 8'-1/2" | 17'0" |

| Impact Location | Results | X - Measurement | Y - Measurement | Speed |
|--------------------|---------|-----------------|-----------------|----------|
| 1 | Pass | 30.00" | 59.75" | 49.9 fps |
| 2 | Pass | 60.38" | 60.50" | 50.0 fps |
| 3 | Pass | 84.625" | 59.50" | 50.0 fps |
| 4 | Pass | 73.00" | 107.50" | 50.1 fps |
| 5 | Pass | 12.50" | 107.25" | 50.0 fps |

Orientation of Missile at Impact was within +/-s* of horizontal. None of the impacts penetrated the specimens.

TAS 201-94/TAS 203-94 - Fatigue Load Cycling

Design Pressure +65.0 psf / -65.0 psf

| Positive % of Test Load | Positive Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) | |
|----------------------------|----------------------------------|---------------------|-----------------------------|--|
| 20% to 50% | 13.0 to 32.5 | 3500 | 2.01 | |
| 0% to 60% | 0.0 to 39.0 | 300 | 2.11 | |
| 50% to 80% | 32.5 to 52.0 | 600 | 2.59 | |
| 30% to 100%* | 19.5 to 65.0 | 100 | 2.87 | |

| Negative % of Test Load | Negative Pressure Range (psf) | Number Of Cycles | Average Cycle Time (Sec) |
|----------------------------|----------------------------------|---------------------|-----------------------------|
| 30% to 100%* | 19.5 to 65.0 | 50 | 2.91 |
| 50% to 80% | 32.5 to 52.0 | 1050 | 2.53 |
| 0% to 60% | 0.0 to 39.0 | 50 | 2.01 |
| 20% to 50% | 13.0 to 32.5 | 3350 | 1.89 |

*Active Panel deflected 3.625" from original plane at 100% Positive load and 4.00" from original plane at 100% Negative load. At the completion of cycles the door panel was operable. There were no tears in the film. In our opinion, the tape and film used to seal for air leakage did not influence the results of the test.

[&]quot;X" measurement is from the left edge of test specimen.

[&]quot;Y" measurement is from the bottom edge of test specimen.

Conditions, Terms, and General Notes Regarding These Tests

The product tested <u>Has Been</u> compared to the detailed drawing, bill of materials and fabrication information supplied by the client so named herein. Our analysis, which includes dimensional and component description comparisons, indicate the tested product and engineering information supplied by the client <u>"Are Equivalent".</u> The report and representative samples will be retained for four years from the date of initial test.

These test results were obtained by employing all requirements of the designated test methods with no Deviations unless explicitly noted in test report. The test results and specimen supplied for testing are in compliance with the reference.

The test results are specific to the product tested by this laboratory and of the sample supplied by the client named herein, and they relate to no other product either manufactured by the client, a fabricator of the client or of the client or of installed field performance.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.

Testing Evaluation Laboratories, Inc. makes no opinions or endorsements regarding this product and its performance. This report may not be reproduced or quoted in partial form without the expressed written approval of Testing Evaluation Laboratories, Inc.

Testing Evaluation Laboratories, Inc.'s letter, reports, its name or insignia or mark are for the exclusive use of the client so named herein and any other use is strictly prohibited. The report, letters and the name of Testing Evaluation Laboratories, Inc., its seal or mark shall not be used in any circumstance to the general public or in any advertising.

Limitation of liability: Due diligence was used in performing the tests and reporting the results. By acceptance of this report, this client agrees to hold harmless and indemnify Testing Evaluation Laboratories, Inc., its employees, sub-contractors, officers and owners against all claims and demands of any kind whatsoever, which arise out of or in any manner connected with the performance of work referred to herein.

Page 7 of 8

Testing Evaluation Laboratories, Inc.

Umany Wright,
Vivian K. Wright,
Procident

President

Florida P.E. # 26686

PF 595 TEL 01991350

Revision Log

| Rev No. | Date | Page(s) | Revision(s) | |
|---------|-----------|---------|-----------------------|--|
| 0 | 6/26/2015 | NA | Original Report Issue | |

| | TABLE OF CONTENTS | | | | | |
|---------|-------------------------------|--|--|--|--|--|
| SHEET # | DESCRIPTION | | | | | |
| 1 | Table of contents | | | | | |
| 2 | Test elevation | | | | | |
| 3 | Horizontal cross sections | | | | | |
| 4 | Horizontal cross sections | | | | | |
| 5 | Horizontal cross sections | | | | | |
| 6 | Vertical cross sections | | | | | |
| 7 | Vertical cross sections | | | | | |
| 8 | Vertical cross sections | | | | | |
| 9 | Vertical cross sections | | | | | |
| 10 | Frame anchoring | | | | | |
| 11 | Sidelite panel detail | | | | | |
| 12 | Components and glazing detail | | | | | |
| 13 | Components | | | | | |
| 14 | Bill of materials | | | | | |

Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL# 01991350 Date 06/26/2015 Verified by ____

| PRODUCT: SPEC. 6C, 6D, 6E PART OR ASSEMBLY: TABLE OF CONTENTS | |
|--|------------------------------|
| BY | |
| DATE REVISIONS | NIS INC. |
| NON | JL! A |
| RW BUILDING CONSULTANTS, INC. 813.659.9197 | W. BUILDING GUNSULIANIS INC. |
| DATE: 4/4/15 SCALE: N.T.S. | ב ר |
| SCALE: N.T.S. DWG. BY: JK | |

Я. Ж.


N 201

DWG. BY: LFS

CHK. BY: DRAWING NO.:

L-7349A

SHEET 1 OF 14



R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 3

BUILDING CONSULTANTS INC. Ν.Ψ. Ŋ 201

4/4/15

N.T.S.

JK

LFS

HORIZONTAL CROSS SECTIONS


PART OR ASSEMBLY:

2

20

50

INTERIOR



DRAWING NO.:

L-7349A SHEET 4 OF 14

Testing Evaluation Laboratories Inc.

Specimen Complies with Drawing Deviations Noted - TEL# 01991350


Date 06/26/2015 Verified by

20


37 33

50

R.W. BUILDING CONSULTANTS INC. 201



CONSULTANTS INC R.W. BUILDING Ŋ



9E VERTICAL CROSS SECTIONS FLEETWOOD SPEC. 6C, 6D, PART OR ASSEMBLY: BY REVISIONS DATE R.W. BUILDING CONSULTANTS INC. NO.

RW BUILDING CONSULTANTS, INC. 813.659.9197

4/4/15 N.T.S. JK DWG. BY: CHK. BY: **LFS** DRAWING NO .:

L-7349A


SHEET 6 OF 14

S 0201

| 1 | | | | | | | | | 1 |
|---|---------------------------|---------------|------------------|-----------|-------------------|-----------|----------------------------|----------------|-----------------------|
| | PRODUCT: | | SPEC. 6C, 6D, 6E | | PART OR ASSEMBLY: | | VEKTICAL CDOSS SECTIONS | CROSS SECTIONS | |
| | | | | | | | BY | | |
| | | | | | | | VO. DATE | REVISIONS | NTS INC. |
| | 0 0 | R ON 81 | SU 3. | LTA 65 | BU NT | ILC S, | INC INC | n ci | DING CONSULTANTS INC. |
| | DATE: 4/4/15 | | | | | | | | |
| | SCALE: N.T.S. | | | | | | | BUIL | |
| | DWG. BY: JK | | | | | | | ≥. | |
| | CHK. BY: LFS DRAWING NO.: | | | | | | r R | | |
| | 510 | | | | 349 | 9A | | | - |
| | SHEET 7 OF 14 | | | | | 320 | | | |

L-7349A SHEET 7 OF 14

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 7



R.W. BUILDING CONSULTANTS INC. 2015

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 9

R.W. BUILDING CONSULTANTS INC. D 201

VERTICAL CROSS SECTIONS

B

DATE

4/4/15 N.T.S.

SHEET 9 OF 14

JK

LFS

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 11

2015 R.W. BUILDING CONSULTANTS INC.

DETAIL

GLAZING

AND

COMPONENTS

B

DATE

JK

LFS

CONSULTANTS INC.

BUILDING

R.W.

Ŋ 201

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 12

CONSULTANTS INC

BUILDING

Α.Ψ.

201

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349A.dwg, 13

| | BILL OF MATER | RIALS | |
|--------|--|-------|----------------------------|
| ITEM # | DESCRIPTION | PART# | MATERIAL |
| В | 2X BUCK SG >= 0.55 | - | WOOD |
| С | 1/4" MAX. SHIM SPACE | - | - |
| F | #10 x 2" PFH WOOD SCREW | - | STEEL |
| G | #8 x 2" PFH WOOD SCREW | - | STEEL |
| 1 | FRAME | 3911 | 6063-T6 ALUM |
| 2 | FRAME SNAP-IN | 3912 | 6063-T6 ALUM |
| 3 | OUTSWING SILL | 3202 | 6063-T6 ALUM |
| 4 | SILL PAN | - | SHEET METAL (ALUMINUM) |
| 6 | SASH | 3902 | 6063-T6 ALUM |
| 7 | 1" GLASS STOP | 3907 | 6063-T6 ALUM |
| 8 | ATLANTIC SEAL CLIP | 3916 | 6063-T6 ALUM |
| 10 | FRAME (FIN) | 3911 | 6063-T6 ALUM |
| 16 | KONA I-MULLION | 3082 | 6063-T6 ALUM |
| 20 | BULB VINYL - MINI (EPDM 70 Durometer) | 25199 | TREMCO, # TX20801E |
| 21 | BULB VINYL - LARGE (EPDM 70 Durometer) | 25031 | TREMCO, # TX19638E |
| 22 | FOAM SEAL | 25196 | EMESBURY, # 32390 |
| 23 | Q-LON FOAM SEAL | 25189 | SCHLEGEL CORP., # Q225T190 |
| 24 | Q-LON FOAM SEAL | 25058 | SCHLEGEL CORP., # Q375T19 |
| 25 | Q-LON FOAM SEAL | 25059 | SCHLEGEL CORP., # QEZ 376 |
| 26 | Q-LON FOAM SEAL | 19120 | SCHLEGEL CORP., # U 5212 |
| 30 | LOCKING HARDWARE (5 point lock) | - | TRUTH |
| 31 | BUTT HINGE | - | SAVIO |
| 32 | BACK UP KIT | 20535 | SAVIO |
| 33 | HINGE BOLT, 8M X 48MM (FOR PANEL) | 25026 | SAVIO |
| 36 | BACK UP PLATE FOR CORNER BLOCK | 25025 | - |
| 37 | MACHINE SCREW NO 10-32, FHP 1.125" | 25074 | STAINLESS STEEL |
| 38 | MACHINE SCREW NO 10-32, FHP .75" | 25073 | STAINLESS STEEL |
| 39 | HEX HEAD CAP SCREW .375-16, 2.250" | 25175 | STAINLESS STEEL |
| 40 | .375-16 SS. HEX NUT | 25023 | STAINLESS STEEL |
| 41 | .375 SPLIT LOCK WASHER | 25024 | STAINLESS STEEL |
| 44 | #8 x 1/2" PFH SMS | - | STEEL |
| 48 | #8 x 1" PFH SMS | - | STEEL |
| 49 | #10 x 3" PFH SMS | - | STEEL |
| 50 | 4" LONG SETTING BLOCK | 18620 | - |
| 52 | ANCHOR BLOCK | - | 6063-T6 ALUM |
| 55 | FIXED SILL BLOCK | - | 6063-T6 ALUM |
| 56 | LATCH AND DEADBOLT STRIKE PLATE | - | - |
| 57 | STRIKE PLATE | - | - |

Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL#_01991350
Date_06/26/2015 Verified by______

| | PRODUCT: FLEETWOOD SPEC. 6C, 6D, 6E | | | | PART OR ASSEMBLY: | | | | |
|--|---|---------|-----|----|-------------------|----|-------------------------------------|-----------|---------|
| | | | | | | | BY | | |
| | | | | | | |). DATE | REVISIONS | |
| | 0 0 | R ON 81 | | 65 | BU NT 9.9 | | 2015 R.W. BUILDING CONSULTANTS INC. | | |
| | DATE: 4/4/15 SCALE: N.T.S. DWG. BY: JK CHK. BY: LFS | | | | | | | | |
| | _ | | BY: | | | JK | | | W. |
| | | | NG | NO | .: 34: | | | | :015 R. |

SHEET 14 OF 14

© 201

| | TABLE OF CONTENTS | | | | | | |
|---------|-------------------------------|--|--|--|--|--|--|
| SHEET # | DESCRIPTION | | | | | | |
| 1 | Table of contents | | | | | | |
| 2 | Test elevation | | | | | | |
| 3 | Horizontal cross sections | | | | | | |
| 4 | Horizontal cross sections | | | | | | |
| 5 | Horizontal cross sections | | | | | | |
| 6 | Horizontal cross sections | | | | | | |
| 7 | Vertical cross sections | | | | | | |
| 8 | Vertical cross sections | | | | | | |
| 9 | Vertical cross sections | | | | | | |
| 10 | Vertical cross sections | | | | | | |
| 11 | Vertical cross sections | | | | | | |
| 12 | Vertical cross sections | | | | | | |
| 13 | Frame anchoring | | | | | | |
| 14 | Sidelite panel detail | | | | | | |
| 15 | Components and glazing detail | | | | | | |
| 16 | Components | | | | | | |
| 17 | Bill of materials | | | | | | |

Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL# 01991350
Date 06/26/2015 Verified by


| | PRODUCT: FLEETWOOD SPEC. 6, 6A | | | | PART OR ASSEMBLY: | PART OR ASSEMBLY: TABLE OF CONTENTS | | | |
|--|---|----|-----|--|-------------------|--|------------------------|-----------|--------------------------------|
| | | | | | | | BY | | |
| The second secon | | | | | | | | REVISIONS | |
| | | | | | | | DATE | | NTS INC. |
| | | | | | | | ž | _ - | ULTAI |
| | BUILDING CONSULTANTS, INC. 813.659.9197 | | | | | | | | R.W. BUILDING CONSULTANTS INC. |
| | DATE: 4/4/15 SCALE: N.T.S. DWG. BY: JK CHK. BY: LFS | | | | | | | | חורם |
| | DW | G. | BY: | | , , | JK | _ | | Α. Β |
| | СН | | BY: | | L | FS | 3 | | Ν. |


CHK. BY: DRAWING NO .:

L-7349

SHEET 1 OF 17

Ŋ 201





Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL#_01991350
Date 06/26/2015 Verified by

HORIZONTAL CROSS SECTION

| PRODUCT: | | SPEC. 6, 6A | 100 Miles 100 Mi | PART OR ASSEMBLY: | THE COLUMN | HORIZONIAL RECEIONIS | CROSS SECTIONS | | |
|----------|-------------------------------|-------------|--|-------------------|------------|-------------------------|----------------|--|--|
| d. | | | | /d | | BY | | | |
| \vdash | | | | | _ | | | | |
| | | | | | | | S | | |
| | | | | | | | REVISIONS | | |
| | | | | | | DATE | | | |
| | | | | | | NO. | | | |
| 0 0 | RW BUILDING CONSULTANTS, INC. | | | | | | | | |

813.659.9197

R.W. BUILDING CONSULTANTS INC.


2015

4/4/15 SCALE: N.T.S.

DWG. BY: JK LFS CHK. BY:

DRAWING NO.: L-7349

SHEET <u>3</u> OF <u>17</u>



Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL# 01991350
Date 06/26/2015 Verified by

1 HORIZONTAL CROSS SECTION

| PRODUCI: | | SPEC. 6, 6A | | PART OR ASSEMBLY: | THE PERSON OF TH | JAINOZINO MOZINO | CACAS SECTION | |
|--|--|-------------|--|-------------------|--|---|---------------|--|
| | | | | | | BY | | |
| | | | | | | | REVISIONS | |
| | | | | | | DATE | | |
| | | | | | | NO. | | |
| RW BUILDING CONSULTANTS, INC. 813.659.9197 | | | | | | | | |

DATE:

SCALE:

DWG. BY:

CHK. BY:

DRAWING NO.:


2015 R.W. BUILDING CONSULTANTS INC.

N.T.S.

L-7349 SHEET <u>4</u> OF <u>17</u>


JK

LFS



CONSULTANTS INC. BUILDING R.W. Ŋ 201

Š.



RW BUILDING CONSULTANTS, INC. 813.659.9197

DATE

R.W. BUILDING CONSULTANTS INC.

2015

HORIZONTAL CROSS SECTIONS

PART OR ASSEMBLY:

FLEETWOOD SPEC. 6, 6A

PRODUCT:

4/4/15 DATE: N.T.S. SCALE: JK


DWG. BY: CHK. BY:

DRAWING NO.: L-7349

SHEET 6 OF 17

LFS

HORIZONTAL CROSS SECTION



EXTERIOR INTERIOR

VERTICAL CROSS SECTION

Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL#_01991350
Date 06/26/2015 Verified by _______

| | | | | | | | REVISION | | |
|--|----|-----|--|---|----|------|----------|--------------------------------|--|
| | | | | | | DATE | | ING. | |
| | | | | | | NO. | | R.W. BUILDING CONSULTANTS INC. | |
| RW BUILDING CONSULTANTS, INC. 813.659.9197 | | | | | | | | | |
| DATE: 4/4/15 CCALE: N.T.S. | | | | | | | | | |
| SCALE: N.T.S. | | | | | | | | | |
| W | G. | BY: | | , | JK | | | > | |
| Н | ĸ. | BY: | | L | FS | 3 | | D. | |
| | | | | | | | | | |

L-7349 SHEET 7 OF 17


Ŋ © 201

DWG. BY:

CHK. BY: DRAWING NO .:

PART OR ASSEMBLY:

PRODUCT:




VERTICAL CROSS SECTIONS PART OR ASSEMBLY: BY DATE 2015 R.W. BUILDING CONSULTANTS INC.

 $\mathcal{R}_{\mathbb{W}_{\mathsf{BUILDING}}}$ consultants, inc. 813.659.9197


4/4/15 DATE: SCALE: N.T.S. JK DWG. BY: LFS CHK. BY:

DRAWING NO.: L-7349

SHEET <u>8</u> OF <u>17</u>



R.W. BUILDING CONSULTANTS INC. 2015




R.W. BUILDING CONSULTANTS INC. Ŋ 201


JK LFS

VERTICAL CROSS SECTIONS

PART OR ASSEMBLY:



© 2015 R.W. BUILDING CONSULTANTS INC.



5 R.W. BUILDING CONSULTANTS INC. 201

DATE

JK LFS

VERTICAL CROSS SECTIONS

PART OR ASSEMBLY:

2" (TYP.)

4" (TYP.)

- 6" (TYP.)

8" (TYP.)

. 2" (TYP.) . 4" (TYP.) . 6" (TYP.)

CONSULTANTS INC. R.W. BUILDING O 2015

REVISIONS

DETAIL

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349.dwg, 15

CONSULTANTS INC. BUILDING R.W. ເດ

201

DATE

4/4/15

L-7349

N.T.S.

JK

LFS

DETAIL

GLAZING

COMPONENTS

PART OR ASSEMBLY:

CONSULTANTS INC.

BUILDING

R.W.

Ŋ

201

R:\Clients\Fleetwood PERMANENT\Drawings\Lab Dwgs\L-7349.dwg, 16

| | BILL OF MATE | RIALS | |
|-------|--|-------|----------------------------|
| ПЕМ # | DESCRIPTION | PART# | MATERIAL |
| В | 2X BUCK SG >= 0.55 | - | WOOD |
| С | 1/4" MAX. SHIM SPACE | - | - |
| F | #10 x 1-1/2" PFH WOOD SCREW | - | STEEL |
| G | #8 x 2" PFH WOOD SCREW | - | STEEL |
| Н | #10 x 2" PFH WOOD SCREW | - | STEEL |
| 1 | FRAME | 3911 | 6063-T6 ALUM |
| 2 | FRAME SNAP-IN | 3912 | 6063-T6 ALUM |
| 3 | OUTSWING SILL | 3202 | 6063-T6 ALUM |
| 4 | SILL PAN | - | SHEET METAL (ALUMINUM) |
| 6 | SASH | 3902 | 6063-T6 ALUM |
| 7 | 1" GLASS STOP | 3907 | 6063-T6 ALUM |
| 8 | ATLANTIC SEAL CLIP | 3916 | 6063-T6 ALUM |
| 10 | FRAME (FIN) | 3911 | 6063-T6 ALUM |
| 16 | KONA I-MULLION | 3082 | 6063-T6 ALUM |
| 17 | KONA FRAME | 3805 | 6063-T6 ALUM |
| 18 | KONA 1" GLASS STOP | 3801 | 6063-T6 ALUM |
| 20 | BULB VINYL - MINI (EPDM 70 Durometer) | 25199 | TREMCO, # TX20801E |
| 21 | BULB VINYL - LARGE (EPDM 70 Durometer) | 25031 | TREMCO, # TX19638E |
| 22 | FOAM SEAL | 25196 | EMESBURY, # 32390 |
| 23 | Q-LON FOAM SEAL | 25189 | SCHLEGEL CORP., # Q225T190 |
| 24 | Q-LON FOAM SEAL | 25058 | SCHLEGEL CORP., # Q375T190 |
| 25 | Q-LON FOAM SEAL | 25059 | SCHLEGEL CORP., # QEZ 376 |
| 26 | Q-LON FOAM SEAL | 19120 | SCHLEGEL CORP., # U 5212 |
| 30 | LOCKING HARDWARE (5 point lock) | - | TRUTH |
| 31 | BUTT HINGE | - | SAVIO |
| 32 | BACK UP KIT | 20535 | SAVIO |
| 33 | HINGE BOLT, 8M X 48MM (FOR PANEL) | 25026 | SAVIO |
| 36 | BACK UP PLATE FOR CORNER BLOCK | 25025 | - |
| 37 | MACHINE SCREW NO 10-32, FHP 1.125" | 25074 | STAINLESS STEEL |
| 38 | MACHINE SCREW NO 10-32, FHP .75" | 25073 | STAINLESS STEEL |
| 39 | HEX HEAD CAP SCREW .375-16, 2.250" | 25175 | STAINLESS STEEL |
| 40 | .375-16 SS. HEX NUT | 25023 | STAINLESS STEEL |
| 41 | .375 SPLIT LOCK WASHER | 25024 | STAINLESS STEEL |
| 44 | #8 x 1/2" PFH SMS | - | STEEL |
| 47 | #10 x 2-1/2" PFH SMS | - | STEEL |
| 48 | #8 x 1" PFH SMS | - | STEEL |
| 49 | #10 x 3" PFH SMS | - | STEEL |
| 50 | 4" LONG SETTING BLOCK | 18620 | - |
| 52 | ANCHOR BLOCK | - | 6063-T6 ALUM |
| 55 | FIXED SILL BLOCK | - | 6063-T6 ALUM |
| 56 | LATCH AND DEADBOLT STRIKE PLATE | - | - |
| 57 | STRIKE PLATE | - | - |

Testing Evaluation Laboratories Inc.
Specimen Complies with Drawing
Deviations Noted - TEL# 01991350
Date 06/26/2015 Verified by

| PRODUCT: | | SPEC. 6, 6A | | PART OR ASSEMBLY: | | BILL OF MAIERIALS | | |
|--|-----|-------------|--|-------------------|-----------|-------------------|-----------|--|
| | | | | | | BY | | |
| | | | | | | | SNC | |
| | | | | | | | REVISIONS | |
| | | | | | | DATE | | |
| | | | | | | ON | | |
| RW BUILDING CONSULTANTS, INC. 813.659.9197 | | | | | | | | |
| DA | TE: | : | | 4/ I.T. | 15 .S. | 5 | | |

DWG. BY:

CHK. BY: DRAWING NO.: © 2015 R.W. BUILDING CONSULTANTS INC.

JK LFS

L-7349 SHEET <u>17</u> OF <u>17</u>