10235 8th Street, Rancho Cucamonga, CA 91730

Report #: T20-117

REPORT SUMMARY

REPORT

T20-117

TESTED FOR

Fleetwood Windows and Doors 1 Fleetwood Way Corona. CA 92879

SERIES & PRODUCT TYPE

Edge $\mid f \mid$ - THERMALLY BROKEN ALUMINUM FIXED WINDOW with Butt Glazed Center (Additional Testing with Vertical Fin)

CONFIGURATION

00

FRAME SIZE

3657.60 mm x 3048.00 mm (144.00" x 120.00")

SPECIFICATION

NAFS - North American Fenestration Standard/specification for windows, doors, and skylights AAMA/WDMA/CSA 101/I.S.2/A440-17

PRIMARY DESIGNATOR

CLASS LC-PG30 3657.60 x 3048.00 mm (144.00 x 120.00 in) Type: FW

TEST COMPLETION DATE

December 2, 2021

REPORT DATE

April 9, 2021

FTL - Phone: 909.477.4343 - www.ftltesting.com

Fenestration Testing Laboratory, Inc. 10235 8th Street, Rancho Cucamonga, CA 91730

Report #: T20-117

1.0 Tested For: Fleetwood Windows and Doors

1 Fleetwood Way Corona, CA 92879

2.0 Purpose:

The purpose of this report is to present the testing methods employed and the test results obtained during the performance testing of one (1) THERMALLY BROKEN ALUMINUM FIXED WINDOW described in paragraph 4.0 of this report.

- 3.0 Test References:
- 3.1 NAFS North American Fenestration Standard/specification for windows, doors, and skylights AAMA/WDMA/CSA 101/I.S.2/A440-17
- 3.2 ASTM F 588-17 Forced Entry Resistance Tests for Windows
- **3.3** CAWM 301-90(1995) Forced Entry Test for Windows (CMBSO 1-79)
- **4.0 Compliance Statement:** The test results in paragraph 6.0 indicate that the test sample described in paragraph 5.0 of this report met the performance requirements of the above specifications for the performance grade shown in 4.1 below.
- **4.1** CLASS LC-PG30 3657.60 x 3048.00 mm (144.00 x 120.00 in) Type: FW
- 5.0 Sample Submitted:

5.1 Product Type: THERMALLY BROKEN ALUMINUM FIXED WINDOW

5.2 Series: Edge | f |5.3 Configuration: 00

5.4 Product Dimensions: Millimeters Inches

Total Frame: 3657.60 x 3048.00 144.00 x 120.00 Fixed DLO (both): 1771.65 x 2921.00 69.75 x 115.00

5.5 Glass and Glazing: Applies to both IGU's

| IGU Thickness | Spacer Width | Interior Lite | Exterior Lite | Glazing method |
|------------------|-----------------|------------------|------------------|--|
| 1.25" | 0.5" | 10 mm | 10 mm | Outside glazed onto EPDM bulb vinyl. |
| overall | | Tempered | Tempered | Setting blocks 0.75" high were set at quarter points on the |
| wide | | _ | _ | sill of each IGU. |
| | | | | Aluminum glazing stop was applied full perimeter on the |
| | | | | outside. |
| | | | | The two IGU's were silicone butt glazed at the center |
| | | | | vertical fin on the interior side of the window. The fin was |
| | | | | adhered to the inside of the IGUs with double side |
| | | | | adhesive "Thermalbond Foam Spacer" structural silicone |
| | | | | on the interior and exterior between IGU's. |

5.6 Weepage:

The sill fit into an aluminum "Arche-Duct" pan drain system with inside and outside vertical legs 1.45" high and ends legs 2.44" high. The pan drain contained three weeps in two configuration. The window passed in both configurations as shown in the drawings.

Configuration #1 – Three ½" NPT couplers coming out the outside face of the pan. Configuration #2 – Three 1" NPT couplers draining down the bottom of the pan.

For each configuration, the weeps were located as follows: One weep hole 7-15/16" from each end and one at midspan.

Page 2 of 5 FTL - Phone: 909.477.4343 – www.ftltesting.com

10235 8th Street, Rancho Cucamonga, CA 91730

Report #: T20-117

5.6 Weepage: (Continued)

The window sill contained a ¼" diameter vertical weep 7-3/4" from each end and 60" on center in the field.

The three sill legs extending down to the pan were notched 1" x 1/4" in line with the pan weeps.

5.7 **Pressure balancing:** None

5.8 Weather-stripping:

| Туре | Quantity | Location |
|------------------------|----------|---|
| Foam-filled bulb vinyl | Two (2) | Sill - one on the outside face, and one on the inside face that |
| - | strips | sealed to the pan. |

5.9 Sealants:

Sealant was applied at the following locations:

- -The glass was bonded to the center vertical fin on the interior on each side of the fin and on the exterior the space between IGUs was filled with structural silicone.
- -The frame corners were sealed full profile.
- -The sill to pan end dam legs were sealed inboard perimeter.
- -The pan vertical upturn leg at each end forming the end dams was formed by bending the pan ends 90 degrees. The resulting vertical joints were sealed full length.
- -Fasteners for the vertical fin were set in sealant.

5.10 Hardware: None

5.11 Construction:

| Location | Joinery Type | Number of Fasteners | Fastener Size |
|--------------------------|---------------------|-----------------------------|--------------------|
| Frame corners | Mechanically joined | Two (2) per corner | #10 x 1" PHP Screw |
| Vertical fin to head and | Mechanically joined | Four (4) screws at each end | #10 x 1" PHP Screw |
| sill | | | |

The sill and head inside glazing legs were integral to their respective extrusions. The jamb inside glazing legs were formed by inserting a snap-in aluminum stop into the jamb inboard channel.

The frame sat in the pan that retained the sill on all four sides.

5.12 Reinforcement:

| Material | Part # | Location | |
|------------------------|--------|------------------------|--|
| 2" x 0.5" Aluminum bar | FW1223 | Fin hollow full length | |

5.13 Installation:

| Location on frame | Anchor type | Spacing |
|-------------------------|-------------------|--|
| The window frame | #8 x 2.5" PFH | Jambs - 6" from each end and 24" on center from each end for |
| jambs and head were | | a total of six (6). |
| fastened to the 2" x 8" | | Head - 6" from each end and two more 24" on center. Also, |
| wooden rough opening. | | one 6" each way from the center line, and one more 6" on |
| | | center; there were ten (10) total screws anchoring the head. |
| The sill pan was suppo | orted in the roug | h opening by blocking the sill pan which would normally be |

The sill pan was supported in the rough opening by blocking the sill pan which would normally be recessed in the substrate.

10235 8th Street, Rancho Cucamonga, CA 91730

Report #: T20-117

6.0 - Test procedures and results: All testing procedures were performed in accordance with the performance requirements of the test specifications referenced in paragraph 3.0 of this report. The number preceding each test listed below refers to the corresponding section in the NAFS.

9.3.2 - Air Infiltration (ASTM E283-04(2012)) - With weeps per Configuration #1 - 1/2" NPT

| Test Description | Results | Allowed | Comments |
|---------------------------------------|-----------------------------|--------------------------|------------------|
| 75 Pa differential pressure | 0.15 L/s*m ² | 1.5 L/s*m ² | 1 |
| 1.57 psf differential pressure | 0.03 cfm/ft ² | 0.30 cfm/ft ² | 1 |
| The tested specimen meets the perform | nance levels specified in A | AAMA/WDMA/CSA 101/I.S | 5.2/A440 for air |
| leakage resistance. | | | |

9.3.2 - Air Infiltration (ASTM E283-04(2012)) - With weeps per Configuration #2 - 1" NPT down

| Test Description | Results | Allowed | Comments | | |
|--|--------------------------|--------------------------|----------|--|--|
| 75 Pa differential pressure | 0.10 L/s*m ² | 1.5 L/s*m ² | 1 | | |
| 1.57 psf differential pressure | 0.02 cfm/ft ² | 0.30 cfm/ft ² | 1 | | |
| The tested specimen meets the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air | | | | | |
| leakage resistance. | | | | | |

9.3.3 - Water Penetration (ASTM E547-00(2016)) (with and without fin)

| Test Description | Results | Allowed | Comments |
|--------------------------|----------------------|----------------------|----------|
| DP30 - 220 Pa (4.59 psf) | No water penetration | No water penetration | 2 |

9.3.4.2 - Uniform Load Deflection at Design Pressure (ASTM E330-14) (without fin)

| Test Description | Results | Allowed | Comments |
|-------------------------------|-----------------|-------------|----------|
| DP30 - 1440 Pa (30.08 psf)Pos | 0.00 mm (0.00") | Report only | 3 |
| DP30 - 1440 Pa (30.08 psf)Neg | 0.00 mm (0.00") | Report only | 3 |

9.3.4.3 - Uniform Load Structural at 1.5 x Design Pressure (ASTM E330-14) (without fin)

| Test Description | Results | Allowed | Comments |
|--------------------------------------|-----------------|-----------------|----------|
| OL for DP30 - 2160 Pa (45.11 psf)Pos | 0.00 mm (0.00") | 2.54 mm (0.10") | 3 |
| OL for DP30 - 2160 Pa (45.11 psf)Neg | 0.00 mm (0.00") | 2.54 mm (0.10") | 3 |

9.3.5 - Forced Entry Resistance (ASTM F588-14 & CAWM 301-90(1995))

| Test Description | Results | Allowed | Comments |
|--------------------------------------|----------|----------|----------|
| ASTM F588 Type D and CAWM 301 Type V | No Entry | No Entry | 5 |

Additional Testing:

9.3.2 - Air Infiltration (ASTM E283-04(2012)) - With weeps per Configuration #1 - 1/2" NPT

| Test Description | Results | Allowed | Comments |
|---------------------------------------|-----------------------------|--------------------------|------------------|
| 300 Pa differential pressure | 0.20 L/s*m ² | 1.5 L/s*m ² | 1 |
| 6.27 psf differential pressure | 0.04 cfm/ft ² | 0.30 cfm/ft ² | 1 |
| The tested specimen meets the perform | mance levels specified in A | AAMA/WDMA/CSA 101/I.S | 5.2/A440 for air |
| leakage resistance. | | | |

9.3.2 - Air Infiltration (ASTM E283-04(2012)) - With weeps per Configuration #2 - 1" NPT down

| Test Description | Results | Allowed | Comments |
|--------------------------------------|-----------------------------|--------------------------|------------------|
| 300 Pa differential pressure | 0.20 L/s*m ² | 1.5 L/s*m ² | 1 |
| 6.27 psf differential pressure | 0.04 cfm/ft ² | 0.30 cfm/ft ² | 1 |
| The tested specimen meets the perfor | mance levels specified in A | AAMA/WDMA/CSA 101/I.S | 5.2/A440 for air |

Page 4 of 5 FTL - Phone: 909.477.4343 – www.ftltesting.com

10235 8th Street, Rancho Cucamonga, CA 91730

Report #: T20-117

9.3.3 - Water Penetration (ASTM E547-00(2016))

| Test Description | Results | Allowed | Comments |
|--------------------------|----------------------|----------------------|----------|
| DP40 - 290 Pa (6.06 psf) | No water penetration | No water penetration | 2 |

9.3.4.2 - Uniform Load Deflection at Design Pressure (ASTM E330-14) (With fin)

| Test Description | Results | Allowed | Comments |
|-------------------------------|------------------|-------------|----------|
| DP30 - 1440 Pa (30.08 psf)Pos | 27.94 mm (1.10") | Report only | 4 |
| DP30 - 1440 Pa (30.08 psf)Neg | 37.08 mm (1.46") | Report only | 4 |

9.3.4.3 - Uniform Load Structural at 1.5 x Design Pressure (ASTM E330-14) (With fin)

| Test Description | Results | Allowed | Comments |
|--------------------------------------|-----------------|------------------|----------|
| OL for DP30 - 2160 Pa (45.11 psf)Pos | 1.02 mm (0.04") | 11.68 mm (0.46") | 4 |
| OL for DP30 - 2160 Pa (45.11 psf)Neg | 1.52 mm (0.06") | 11.68 mm (0.46") | 4 |

Comment #1 – Air infiltration passed with and without the fin at 1.57 psf and at 6.27 psf.

Comment #2 - Fixed window did not have an insect screen. Water penetration passed with and without the fin up to 6.06 psf.

Comment #3 - Deflection measurement with the fin removed were taken from frame jamb between fasteners 24" apart.

Comment #4 - Deflection measurement taken from vertical fin.

Comment #5 - FER per ASTM F588 passed grade 10.

Testing was witnessed by: Corey Jones with Fleetwood and Jim Cruz with FTL.

For a complete description of the tested sample, refer to the attached three (3) pages consisting of bill of materials, cross section drawings, and individual part drawings. This report is complete only when all the above referenced bill of materials and drawings are attached.

The bill of materials, cross section drawings, and individual part drawings of frame and sash members are on file and have been compared to the sample submitted. Test sample sections, bill of materials, drawings and a copy of this report will be retained at the test laboratory for four years.

This test report may not be modified in any way without the written consent of Fenestration Testing Laboratory, Inc. (FTL).

The preceding test results relate only to the tested specimen and were obtained by using the applicable test methods listed in section 3.0 and 6.0 above. This report does not constitute certification of this product or an endorsement by this laboratory. It is the property of the client named in section 1.0 above. Certification can only be granted by an approved administrator and/or validator.

TEST COMPLETION DATE: December 2, 2020

REPORT DATE: April 9, 2021

Pete Cruz - Test Engineer

Jim Cruz - Laboratory Manager

Page 5 of 5

FTL - Phone: 909.477.4343 - www.ftltesting.com

TABLE OF CONTENTS

SHEET NO. 1. GENERAL NOTES, DESIGN LOADS, FRAME ANCHOR TABLE AND

SPECIMEN D1 ELEVATION
2. DETAILS
3. DETAILS
4. BILL OF MATERIALS

TEST SPECIMEN


1. SERIES / MODEL: EDGE | f | 2. PRODUCT TYPE: FIXED WINDOW WITH SUB-SILL

GENERAL NOTES

1. BUCKING OPENINGS & BUCKING FASTENERS MUST SE PROPERLY DESIGNED & INSTALLED TO TRANSFER LOADS TO THE STRUCTURE AND TO BE REVIEWED BY BUILDING OFFICIAL.
2. ALL HARDWARE & FASTENERS SHALL BE IN ACCORDANCE WITH THESE DRAWINGS & MAY NOT VARY UNLESS SPECIFICALLY MENTIONED ON THE DRAWINGS.
3. MATERIALS, INCUDING BUT NOT LIMITED TO STEEL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF AAMA AND BUILDING CODE.

SPECIFICATIONS

1. AAMAWDMA/CSA 101/I.S.2/A440-11; A440 S1-09 (CANADIAN SUPPLEMENT) - (NON-IMPACT GLAZING)



CORNERS CONSTRUCTION

1, FRAME CORNER: THE HEAD AND SILL ARE BUTTED TO THE JAMBS AND ATTACHED WITH SCREWS.

GLAZING

G1: 1.25": CLEAR 10mm-T, 0.50 AIR, CLEAR 10mm-T

| OPENING TYPE (SUBSTRATE) | FRAME TO OPENING FASTENER TYPE | MINIMUM EMBEDMENT |
|-------------------------------|-----------------------------------|----------------------|
| 2X_ WOOD FRAME OR BUCK | (1) NO. 8 SMS SCREW | 1 1/2" |
| MIN. 18 GA. 33 KS) STEEL STUD | (1) NO. 8 SMS SCREW | FULL |
| CMU/CONCRETE | (2) 3/16" CONCRETE SCREWS | 1 1/4" |

W/OUT FIN

| AIR INFILTRATION TABLE | | |
|------------------------|--------------|---------|
| RATE | TYPE | READING |
| LOW | INFILTRATION | |
| | EXFILTRATION | |
| HIGH | INFILTRATION | |
| 111011 | EXFILTRATION | |

| WATER | PRESSU | RE TABLE |
|-------|-----------|----------|
| PR | ESSURE (P | SF) |

| | DESIGN P | RESSURE TAE | BLE |
|---------------|----------|----------------------|----------|
| MAX 2 LITE | MAX | DESIGN PRESSURE (PSF | |
| N.F.W. | N.F.H. | POSITIVE | NEGATIVE |
| 144" | 120" | | |

FIN W/ ALUM. INSERT

| | AIR INFILTRATIO | N TABLE |
|------|-----------------|---------|
| RATE | TYPE | READING |
| LOW | INFILTRATION | |
| | EXFILTRATION | |
| HIGH | INFILTRATION | |
| | EXFILTRATION | |

| WATER PRESS | URE | TABLE |
|-------------|-------|-------|
| PRESSURE | (PSF) | |
| | | |

| | DESIGN PRESSURE TABLE | | | | |
|---------------|-----------------------|-----------------------|----------|--|--|
| MAX 2 LITE | MAX | DESIGN PRESSURE (PSF) | | | |
| N.F.W. | N.F.H. | POSITIVE | NEGATIVE | | |
| 144" | 120" | | | | |

FENESTRATION TESTING LAB

REPORT NO:

T20-117

DATE:


FLEETWOOD WAY
CORONA, CA 92879
WIND WE & DOORS www.feetwoodusa.com

CU 12/1/20 JOB NUMBER:


FW EDGE | f | Cert EDGE


SCALE : 3/4" = 1" DRAWING NO. 1


> SHEET : 1 OF 3




| NO. | PART NO. | PART DESCRIPTION | VENDOR NAME | VENDOR PART NO. |
|-----|----------|-------------------------|----------------|--------------------|
| | | ALUMINUM EXTRUSIONS | | |
| 1 | Ef0001 | HEAD / SILL | SIERRA | 700785 |
| 2 | Ef0002 | JAMB | SIERRA | 700786 |
| 3 | Ef0003 | FIN | SIERRA | 700787 |
| 4 | FW1223 | 0.5"x2" ALUMINUM | NUCOR | |
| | | GLASS WEDGES | | |
| 5 | Ef0004 | JAMB WEDGE | SIERRA | - |
| 6 | Ef0006 | 1.25" GLASS WEDGE | SIERRA | 906494 |
| | | MISCELLANEOUS | | |
| 7 | 25031 | LARGE BULB VINYL (EPDM) | TREMCO | TX19638E |
| 8 | 25189 | Q-LON FOAM SEAL | SCHLEGEL | Q225T190 |
| 9 | 26829 | SETTING BLOCK | RYKO | R11639 |
| 10 | 26806 | THERMALBOND FOAM SPACER | SECON RUBBER | V2108 |
| 11 | - | ARCHE-DUCT | LINDBLADE | CUSTOM |











FLEETWOOD WAY CORON, CASSON WAY SENDODS WAY SENDODS CORON, CASSON WAS SENDED SON WAS SENDODS SON WAS SENDON WAS SE


CUSTOMER: PW
JOB NAME EDGE | F| Cent

SCALE : 1'=1' DRAWING NO.

SHEET:










JAMB WEDGE




1.25" GLASS WEDGE



LARGE BULB VINYL

| 0.22 | |
|------|--|
| 8 | |


Q-LON FOAM SEAL



| NO. | PART NO. | PART DESCRIPTION | VENDOR NAME | VENDOR PART NO. |
|-----|----------|-------------------------|----------------|--------------------|
| | | ALUMINUM EXTRUSIONS | | |
| 1 | Ef0001 | HEAD / SILL | SIERRA | 700785 |
| 2 | Ef0002 | JAMB | SIERRA | 700786 |
| 3 | Ef0003 | FIN | SIERRA | 700787 |
| 4 | FW1223 | 0.5"x2" ALUMINUM | NUCOR | |
| | | GLASS WEDGES | | |
| 5 | Ef0004 | JAMB WEDGE | SIERRA | - |
| 6 | Ef0006 | 1.25" GLASS WEDGE | SIERRA | 906494 |
| | | MISCELLANEOUS | | |
| 7 | 25031 | LARGE BULB VINYL (EPDM) | TREMCO | TX19638E |
| 8 | 25189 | Q-LON FOAM SEAL | SCHLEGEL | Q225T190 |
| 9 | 26829 | SETTING BLOCK | RYKO | R11639 |
| 10 | 26806 | THERMALBOND FOAM SPACER | SECON RUBBER | V2108 |
| 11 | | ARCHE-DUCT | LINDBLADE | CUSTOM |



THERMALBOND FOAM SPACER



 $\langle 10 \rangle$ ARCHE-DUCT (PAN DRAIN SYSTEM)

FENESTRATION TESTING LAB T20-117 REPORT NO: DATE:



AWN BY:

FLEETWOOD VAY
CORONA, CA 22379
WINDOWS & DOORS www.fleetwoodsa.com

SCALE : 1'=1'

1 OF 3